



CHABOT- LAS POSITAS COMMUNITY COLLEGE DISTRICT

Purchasing and Warehouse Services Department

August 23, 2007

Addendum No. 5

INVITATION FOR BID No. 08-01 Athletic Facilities Renovation, Chabot College

All Prospective Bidders:

This Addendum modifies the original Bid Documents for the above Bid. Acknowledge receipt of this addendum in the space provided on the **SIGNATURE FORM**. Failure to do so may subject Bidder to disqualification.

The original Bid Documents are modified by the additional information as follows:

Item No.	Location in Contract Documents, Specifications and Drawings	Description
1	Sheet F0.1, Fire Alarm System Description	The new fire alarm system shall be connected to the existing Fluid Controls Institute (FCI) fire alarm system. The existing fire alarm company for Chabot College is Pacific Power and Systems, 6750 Goodyear Rd., Benicia, CA 94510 and their phone number is 707-437-2300.
2	Height of Backstop and Outfield Fencing	Existing height of the baseball backstop and outfield shall be field verified. The approximate heights of the backstop and outfield fencing are 30 feet and 6 feet, respectively.
3	Sheet D5.01, Detail D and Specification Section 02870, Backstop Padding	Add to the specifications: Item U, Description: Backstop Padding (3'H x 8'L); Manufacturer: Tomark Sports; Model #: K11572, Finish/Color: Blue, Distributor/Contact: Tomark Sports, 1-800-959-1844, http://www.tomark.com/BaseballStore/products.cfm?Start=1&Category=102&CategoryName=Backstop_Padding

4	Sheet L6.1, Callout Tree Grate – Type 2, (9) Typ. and Sheet D3.0, Detail M. Sheet L6.1, Callout Tree Grate – Type 1, (7) Typ. and Sheet D3.0, Detail L.	The supplier for the tree grates (5’x10’ and 5’x5’) is Park Pacific, P.O. Box 4999, Walnut Creek, CA 94596. Their phone number is 888-460-7275 and their fax is 888-461-7275. The product is the “Locust” pattern. All mounting and framing shall be per the supplier’s specifications.
5	Section 02510 3.07 Tolerances	The finished surface parallel with the Tennis Court center line shall not vary more than 0.02 of a foot at any point and the transverse slope of the finished surface shall not vary more the 0.02 of a foot.
6	Sheet L6.3, Gates between Backstop and Fencing at Dugout to be demolished and replaced	The gates will remain and reattach as is between Backstop and Fence – Type 2.
7	Sheet L6.3, Concrete Band @ fencing to be demolished and replaced	The concrete band will be demolished with the fencing and replaced with a 2’ wide by 6” deep concrete edgeband with 2 ~ #4 horizontal rebars running longitudinally.
8	Addendum #2, DA #11	The Intermediate Fence – Type 1 is a frame for netting to be hung from. There is no need for a gate between the two batting cage stations. Passage will be through the netting at the batting end of the cage.
9	Addendum #2, Item #14, referring to Sheet L1.1, Existing Irrigation Controllers and Sheet L7.1, New Irrigation Controller	The existing controllers are located at the northwest corner of the existing storage shed in the corp yard. The new location for the controller is the southwestern corner of the Operations & Maintenance Building.
10	Sheet L2.2, Sheet Notes: (Concession Plan) and Specification 11600, Part 2, 2.01	The Sheet Notes on Sheet A2.2 control over the specifications and the items marked N.I.C. will not be included in this bid.
11	Bid Alternate #3, Football Field Lighting Improvements	All improvements associated with this bid alternate is limited to the removal of the existing maintenance basket, lighting fixtures, brackets, and crossarms, and the reinstallation of the new lamp fixtures and crossarm assemblies as noted in drawings provided per Addendum #2.

If you have any questions regarding this Addendum No.5, please contact the Office of the Facilities Planning & Management in **writing**, via facsimile or email.

All other terms and conditions of BID No. 08-01 to remain the same.

END OF ADDENDUM No.5